



NOTES:

1. PRESSURE TREATED No. 1 SOUTHERN PINE.
2. ALL BOLTS SHALL BE RECESSED. USE GALVANIZED $\frac{5}{16}$ " LAG BOLTS FOR 2"x6" TO 4"x6" CONNECTIONS, AND $\frac{1}{4}$ " GALVANIZED LAG BOLTS FOR ALL OTHERS.
3. STAIN WITH ONE COAT OF TWP CALIFORNIA CEDAR.
4. MINIMUM 2 FEET CLEAR BETWEEN RAILING & TRAIL EDGE.



EFFECTIVE:07/01/23

**STANDARD STEEL BEAM & WOOD (OPTION B)
BRIDGE RAILING EXTENSION**

DETAIL No.

9500.04