



**NOTES:**

1. THE PLUMBING CONTRACTOR TYPICALLY SUPPLIES INLET, OUTLET, BAFFLE WALL TEE AND INSTALLS SLOPE IN SAMPLE VAULT. SEE INLET AND OUTLET SANITARY TEE DETAILS AND SAMPLE VAULT DETAILS FOR DESIGN SPECIFICS.
2. GROUTING OF BAFFLE WALL BOTTOM AND SIDES IS REQUIRED ON ALL NON-FIXED BAFFLE WALLS.
3. GROUTING AROUND INLET TEE, OUTLET TEE, BAFFLE TEES AND SAMPLE VAULT WALL PENETRATIONS IS REQUIRED.
4. SUPPORT STRAP(S) ON TEES MAY BE REQUIRED.

CARY

GREASE INTERCEPTOR

NOT TO SCALE