



Final Report

**Town of Cary**

**2010 Wastewater Collection System Study and Master Plan**

June, 2013



Project No. 30508-001

**HAZEN AND SAWYER**  
Environmental Engineers & Scientists

This page is intentionally left blank



## TABLE OF CONTENTS

<b>EXECUTIVE SUMMARY .....</b>	<b>1</b>
<b>Section 1 - Introduction .....</b>	<b>1-1</b>
1.1 Project Background.....	1-1
1.2 Objectives and Scopes .....	1-1
1.3 Organization of Report .....	1-2
<b>Section 2 - Existing Wastewater System .....</b>	<b>2-1</b>
2.1 Introduction .....	2-1
2.2 Service Boundary Dilenation.....	2-7
2.3 Water Reclamation Facilities (WRFs).....	2-9
2.3.1 North Cary WRF .....	2-9
2.3.2 South Cary WRF .....	2-13
2.3.3 Triangle WWTP .....	2-13
2.3.4 Western Wake Regional Wastewater Reclamation Facility (WWRWRF) .....	2-16
2.3.5 Per Capita Wastewater Flows.....	2-16
2.4 Wastewater Collection System.....	2-22
2.4.1 North Cary System .....	2-22
2.4.2 South Cary System .....	2-24
2.4.3 West Cary System .....	2-24
2.4.4 RDU International Airport.....	2-24
2.4.5 RTP South.....	2-24
2.5 Current O&M Practices.....	2-28
2.5.1 Pump Stations.....	2-28



2.5.2	Collection System .....	2-28
2.5.3	Permanent Flow Meters .....	2-29
2.5.4	Peak Wet Weather Management.....	2-32
<b>Section 3 - Pump Station Inspection and Evaluations.....</b>		<b>3-1</b>
3.1	Introduction .....	3-1
3.2	Pump Station Flow Tests.....	3-1
3.2.1	Odor Samples.....	3-8
3.2.2	Noise Readings.....	3-8
3.3	Odor Control Technology Overview .....	3-13
3.3.1	Chemical Scrubbers .....	3-14
3.3.2	Biofilters.....	3-16
3.3.3	Carbon Adsorption.....	3-18
3.3.4	Chemical Addition.....	3-19
3.3.5	Recommendation .....	3-23
<b>Section 4 - Population and Flow Projections.....</b>		<b>4-1</b>
4.1	General .....	4-1
4.2	Projection Methodology.....	4-1
4.3	Flow Projection .....	4-2
<b>Section 5 - Inflow and Infiltration Analysis .....</b>		<b>5-1</b>
5.1	Introduction .....	5-1
5.2	Background .....	5-1
5.2.1	Average Base Flow (ABF) .....	5-8
5.2.2	Comparing Water Consumption Data .....	5-19
5.2.3	Rainfall-Dependent Inflow and Infiltration (RDI/I).....	5-25



**Section 6 - Hydraulic Capacity Analysis..... 6-1**

6.1 Model Selection.....6-1

6.2 Model Development.....6-1

6.3 Wet-Weather Flow Determination.....6-5

6.4 Model Calibration and Verification.....6-5

6.5 Existing Capacity Analysis .....6-9

6.6 Methodology in Simulating Future System .....6-12

6.7 Model Results and System Improvement.....6-13

6.8 Northwest Cary Force Main Project .....6-18

6.9 Further Consolidation of Previously Morrisville-owned System .....6-18

**Section 7 - Capital Improvement Program..... 7-1**

7.1 General .....7-1

7.2 Unit Cost .....7-21

7.3 Project Description .....7-22

7.3.1 Projects Starting in Phase I (2011 to 2015) .....7-22

7.3.2 Projects Starting in Phase II (2015-2025) .....7-26

7.3.3 Projects Starting in Phase III (2025 to Build-Out).....7-27

7.4 Conclusion and Recommendations .....7-31

**Section 8 - Regulatory Considerations..... 8-1**

8.1 General .....8-1

8.2 Sanitary Sewer Overflow (SSO) Regulations and “CMOM” .....8-1

8.2.1 Sanitary Sewer Overflows (SSOs) and Capacity, Management,  
and Operations and Maintenance (CMOM).....8-1

8.2.2 Sanitary Sewer Overflow and CMOM Requirements .....8-3

8.2.3 North Carolina DENR Wastewater Collection System Requirements .....8-4



TABLE OF CONTENTS

---

8.2.4 NPDES Stormwater Phase II.....8-7

8.2.5 Local Programs for Sewer Systems.....8-9

8.2.6 Planning Coordination .....8-9

8.2.7 Interbasin Transfer Requirements.....8-11

8.2.8 Summary of Regulatory Concerns .....8-12

**Section 9 - Collection System Telemetry and SCADA Issues.....9-1**

**Section 10 - Conclusions and Recommendations ..... 10-1**

10.1 Conclusions .....10-1

10.2 Recommendations.....10-2



## LIST OF TABLES

Table ES-1: Summary of Total Water Demand vs. Average Base Flow Comparison .....	4
Table ES-2: Incremental Water Demand Increase from Water System Master Plan .....	4
Table ES-3: Long-Term Wastewater Flow Projections.....	5
Table ES-4: Pump Station Test Results .....	6
Table ES-5: GWI for Flow Meters.....	9
Table ES-6: Capital Improvement Program.....	13
Table 2-1: Lengths of Gravity Pipes by Size .....	2-3
Table 2-2: Length of Force Main Pipes by Size .....	2-4
Table 2-3: Yearly Average Daily Wastewater Flows to Three WRFs Serving the Town of Cary’s Collection System.....	2-11
Table 2-4: North Cary System – Pump Stations.....	2-12
Table 2-5: South Cary System – Pump Stations.....	2-14
Table 2-6: West Cary System – Pump Stations.....	2-15
Table 2-7: Historical Per Capita Wastewater Flows.....	2-19
Table 2-8: Details of Permanent Flow Meters in the Town of Cary .....	2-31
Table 3-1: Results of Pump Drawdown Test.....	3-2
Table 3-2: Results of Odor Tests .....	3-9
Table 3-3: Typical Noise Levels .....	3-11
Table 3-4: Results of Noise Tests .....	3-12
Table 3-5: Odor Control Measure at each Pump Station .....	3-20
Table 4-1: ABF/Total Water Demand Ratios.....	4-2
Table 4-2: Future Water Demand Increases Compared to 2010.....	4-3
Table 4-3: Future Wastewater Flow Projections .....	4-3
Table 5-1: Service Area Inventory Data for Flow Meters .....	5-3
Table 5-2: Average Monthly GWI for all Meters in 2010.....	5-11
Table 5-3: GWI Among All Meter Basins.....	5-17
Table 5-4: Classification of Water Demand by Service Type .....	5-19
Table 5-5: Sewer Return Ratio of Flow Meters.....	5-20
Table 5-6: Monthly Maximum Depth Reading and Surcharge for All Flow Meters from Jan 2008 to April 2010.....	5-27
Table 5-7: RDI/I Volume for All Flow Meters During the 6/16/2009 Event.....	5-37
Table 6-1: Dry Weather Flow Calibration .....	6-6
Table 6-2: Wet Weather Calibration.....	6-7
Table 6-3: R Values for All Basins.....	6-8
Table 6-4: Determination of Peaking Factor.....	6-12



TABLE OF CONTENTS - LIST OF TABLES

---

Table 6-5: Pump Station Capacity.....	6-16
Table 7-1: Gravity Interceptor, Force Main Build-out Flows and Capacity.....	7-3
Table 7-2: Evaluation of 2003 Report Recommendation Gravity Interceptor and Force Main ....	7-7
Table 7-3: Pipeline Unit Construction Cost.....	7-21
Table 7-4: Summary of Capital Improvement Program.....	7-29





## LIST OF FIGURES

Figure ES-1: Illustration of the Existing Sewer Collection System Owned and Serviced by the Town of Cary..... 3

Figure 2-1: Overview of the Existing Sewer Collection System Owned and Serviced by the Town of Cary ..... 2-2

Figure 2-2: Total Wastewater Flows from the Town of Cary’s Service Area (2004-2010) ..... 2-5

Figure 2-3: Illustration of Morrisville-Owned Sewer System Prior to the Merger ..... 2-6

Figure 2-4: Illustration of Sub-basin Delineation ..... 2-8

Figure 2-5: Historical Daily Wastewater Flows to the North Cary WRF (2001-2010)..... 2-10

Figure 2-6: Historical Wastewater Flow Data for the South Cary WRF (2004-2010)..... 2-17

Figure 2-7: Total Wastewater Flow for the West Cary Service Area (2004-2010)..... 2-18

Figure 2-8: Historical Population Trends in the Towns of Cary and Morrisville ..... 2-20

Figure 2-9: Historical Per Capita Wastewater Flows..... 2-21

Figure 2-10: Schematic of the North Cary Service Area ..... 2-23

Figure 2-11: Schematic of the South Cary Service Area ..... 2-25

Figure 2-12: Schematic of the West Cary Service Area ..... 2-26

Figure 2-13: Historical Daily Average Flows from RDU Airport ..... 2-27

Figure 2-14: Permanent Flow Meter Locations in the Town of Cary’s Sewer Service Area ..... 2-30

Figure 2-15: Illustration of Flow Switching Between the North Cary and West Cary Service Areas Via Kit Creek Pump Station ..... 2-33

Figure 2-16: Illustration of Flow Switching Between the North and West Cary Service Areas via Four Inactive Pump Stations ..... 2-34

Figure 2-17: Illustration of Flow Switching Between the North and South Cary Service Areas .. 2-35

Figure 3-1: Typical Wet Well Section ..... 3-5

Figure 3-2: Comparison of Pump Stations Tested in 2001 vs. in 2010 ..... 3-7

Figure 3-3: One-Stage Packed Bed Chemical Scrubber ..... 3-15

Figure 3-4: Multi-stage Packed Bed Chemical Scrubber..... 3-16

Figure 3-5: Tower Type Biofilter ..... 3-18

Figure 3-6: Carbon Odor Scrubber..... 3-19

Figure 3-7: Passive Canister Carbon Scrubber ..... 3-19

Figure 5-1: Service Area Diagram of Town of Cary’s Sewer Collection System (on Individual Meter Basins) ..... 5-5

Figure 5-2: Sewer Length Diagram of Town of Cary’s Sewer Collection System (on Individual Meter Basins) ..... 5-6

Figure 5-3: Inch-Mile Diagram of Town of Cary’s Sewer Collection System (on Individual Meter Basins) ..... 5-7



Figure 5-4: Components of Average Base Flow .....5-10

Figure 5-5: Average Monthly GWI in 2010 (Meters 1, 2, 4, 5, 7 and 8).....5-13

Figure 5-6: Average Monthly GWI in 2010 (Meters 9, 10, 13, 17, 18, 22, 23, 24, 25 and 26) .....5-14

Figure 5-7: Average Monthly GWI in 2010 (Meters 11, 12, 14, and 16).....5-15

Figure 5-8: Average Monthly GWI in 2010 (Meters 3 and 15) .....5-16

Figure 5-9: Flow Diagram of Upstream Water Demand vs. ADSF .....5-22

Figure 5-10: Flow Diagram of ADSF vs. GWI .....5-23

Figure 5-11: Flow Diagram for Sewer Return Ratio .....5-24

Figure 5-12: Illustration of RDI/I .....5-26

Figure 5-13: Numbers of Months from January 2008 to April 2010 Showing Surcharge for Each  
Meter.....5-29

Figure 5-14: Plan View of Meter 22/23 In Reference to Aviation Parkway Pump Station .....5-30

Figure 5-15: Level Readings for Meters 22, 23 and 24 During 6/16/2009 Wet Weather Event ..5-31

Figure 5-16: Velocity Readings for Meters 22, 23 and 24 During 6/16/2009 Wet Weather Event.5-  
32

Figure 5-17: Flow Data for Meters 2, 4, and 5 During 6/16/2009 Event .....5-33

Figure 5-18: Depth Readings for Meters 2, 4 and 5 During 6/16/2009 Event.....5-34

Figure 5-19: Velocity Readings for Meters 2, 4 and 5 During 6/16/2009 Event.....5-35

Figure 5-20: Flow Readings for Meters 3 and 16 During 6/16/2009 Event .....5-39

Figure 5-21: Level Readings for Meters 3 and 16 During 6/16/2009 Event .....5-40

Figure 5-22: Velocity Readings for Meters 3 and 16 During the 6/16/2009 Event .....5-41

Figure 5-23: Flow Readings for Meters 6 and 7 During the 6/16/2009 Event.....5-43

Figure 5-24: Level Readings for Meters 6 and 7 During the 6/16/2009 Event .....5-44

Figure 5-25: Velocity Readings for Meters 6 and 7 During the 6/16/2009 Event .....5-45

Figure 6-1: Example of Dispersed ABF Assignment Using Water Billing Data in 2010 .....6-3

Figure 6-2: Example of Model Simplification .....6-4

Figure 6-3: Existing Dry Weather System Capacity.....6-10

Figure 6-4: Existing Wet Weather System Capacity.....6-11

Figure 6-5: Recommended Capital Improvement Projects from 2010 to Build-out .....6-15

Figure 6-6: Overall View of Potential Areas to Shift from Morrisville System to Cary System....6-19

Figure 6-7: Potential Areas to Shift from Morrisville System to Cary System - Area A .....6-20

Figure 6-8: Potential Areas to Shift from Morrisville System to Cary System - Area B .....6-21

Figure 6-9: Potential Areas to Shift from Morrisville System to Cary System - Area C .....6-22

Figure 7-1: Comparison of Recommendation with 2003 Master Plan for Wastewater Collection  
System in the Town of Cary .....7-2

Figure 7-2: Crabtree Creek Interceptor A .....7-32

Figure 7-3: Crabtree Creek Interceptor B .....7-33

Figure 7-4: Long Branch .....7-34



TABLE OF CONTENTS - LIST OF FIGURES

Figure 7-5: Lynn’s Branch..... 7-35

Figure 7-6: Nancy Branch..... 7-36

Figure 7-7: Speight Branch..... 7-37

Figure 7-8: Crabtree Creek (Upper) ..... 7-38

Figure 7-9: York Interceptor..... 7-39

Figure 7-10: Harrison Oaks ..... 7-40

Figure 7-11: Dutchman’s Branch Interceptor ..... 7-41

Figure 7-12: Rocky Branch Pump Station and Related Sewers..... 7-42

Figure 7-13: Green Level Interceptor..... 7-43

Figure 7-14: Reedy Creek Regional Pump Station and Related Gravity Sewers ..... 7-44

Figure 7-15: Details of Green Level Force Main..... 7-45

Figure 7-16: Details of Alston Force Main ..... 7-46

Figure 7-17: Reedy Creek Pump Station Expansion..... 7-47

Figure 7-18: Kit Creek Pump Station Upgrade ..... 7-48

Figure 7-19: Morris Branch Pump Station Upgrade..... 7-49

Figure 7-20: Walnut Creek Pump Station Upgrade ..... 7-50

Figure 7-21: Aviation Parkway Pump Station Upgrade..... 7-51

Figure 7-22: Blanche Pump Station Upgrade..... 7-52

Figure 7-23: Cross Roads Pump Station Upgrade ..... 7-53

Figure 7-24: Swift Creek Interceptor A ..... 7-54

Figure 7-25: Swift Creek Interceptor B ..... 7-55

Figure 7-26: Swift Creek Interceptor C ..... 7-56

Figure 7-27: Swift Creek Interceptor D ..... 7-57

Figure 7-28: Upper Kit Creek Interceptor ..... 7-58

Figure 7-29: Circadian Court Pump Station Upgrade..... 7-59

Figure 7-30: Campbell Branch..... 7-60

Figure 7-31: The Reserve (Upper)..... 7-61

Figure 7-32: Upper Swift Creek Interceptor ..... 7-62

Figure 7-33: Pump Station No. 1 and Force Main..... 7-63

Figure 7-34: New Pump Station No. 2 and Force Main ..... 7-64

Figure 7-35: New Pump Station No. 3 and Force Main ..... 7-65

Figure 7-36: Terrington Pump Station Upgrade ..... 7-66

Figure 7-37: Upper Crabtree Creek Pump Station..... 7-67

Figure 7-38: Westwood Park Pump Station Abandonment ..... 7-68

Figure 7-39: New Paramount Gravity Sewer ..... 7-69



This page is intentionally left blank