#### Town of Cary Pump Station Inspection Sheet

Facility Name: Walnut Creek PS Inspection Date: 3/10/2010

ID Number: 002

Pump Condition: Good

Type: Submersible Pump One: 1,788 gpm Discharge Diameter: 18" Pump Two: 2,437 gpm Control: **RVAT** Pump Three: 2,065 gpm Motor Horsepower: 25 Firm Capacity 2,672 gpm

Pump RPM: 1750 Design Point (flow): 2700 gpm

Model: AF 1600 Design Point (pressure): 138 feet of water

Manufacturer: ABS Pumps Rep: Pete Duty & Associates

203-238-2700 919-220-4156

Wetwell: 20' by 12' 5' Deep Vol: 9,000 gal

Odor:

At the Fence: 0.002 ppm Wetwell: 0.210 ppm

Odor Control: Ferrous Sulfate/Biofilter Condition: Good

**Generator:** 

Generator: Condition: Good Marathon Electric 938 KVA Model 573RSL2053A-P318W 750 KW

**Grinder:** 

Grinder with bar screen by-pass Condition: Fair


Sound:

At the Fence: 69 dB Gen off Wetwell: 77 db Pump off At the Fence: 81 dB Gen on Wetwell: 76 db Pump on

#### Comments:

- Building trim needs paint to prevent rot.
- Wetwell does not appear to be coated, but appear to be in good condition.
- Pump guides in good condition. Steel guide supports are in fair condition.
- Valves in valve vault has surface rust.
- Valve vault is damp.
- Inside pump control panel is showing its age.
- Concrete side walk stained by Ferrous Sulfate (Cosmetic only).
- Chemical pump looks newer and has only cosmetic defects. Older pump appears to be close to the end of its life cycle.
- Top rung of the grinder manhole entrance is broken
- Biofilter is working. H<sub>2</sub>S level on top on the filter was 0.004 ppm.
- Rain runoff is getting into the Generator enclosure.
- Paint and grout defects on crane and crane base.





# Town of Cary Pump Station Inspection Sheet



### Walnut Creek Pump Station



Control Panel



Crane



Crane Base



Odor Control



Crane Base



# Town of Cary Pump Station Inspection Sheet

Walnut Creek Pump Station



Wetwell



Valves



Grinder



Bar Screen



Chemical Pump



Chemical Pumps

